

## Metropolitan Regional Roads Group Program - 2021/2022 - Summary of Projects

Site	Location	Recommended treatment	MRRG contribution 2/3	City contribution 1/3	Total project cost
1	Kalamunda Road, MV, Road Rehabilitation, 100m West of Terrigal Place to 70m East of Gooseberry Hill Rd/Hawtin Rd, SLK 3.18 - 3.79	Stabilise 210mm foamed bitumen & 40mm 14mm / 75 DG Asphalt	\$354,233	\$177,116	\$531,349
2	Kalamunda Road, MV, Road Rehabilitation, 70m East of Gooseberry Hill Rd/Hawtin Rd to 40m West of Gooseberry Hill Road/Hawtin Road, SLK 3.79 - 3.90	Stabilise 280mm foamed bitumen & 40mm 14mm / 75 DG Asphalt CRM	\$152,963	\$76,481	\$229,444
3	Dundas Road , HW, Road Rehabilitation, 50m South of Abernethy Rd to 80m North of Wittenoom Rd, SLK 0.05 - 0.51	Stabilise 200mm foamed bitumen & 40mm 14mm / 75 DG Asphalt	\$221,519	\$110,760	\$332,279
4	Canning Road, LM, Road Rehabilitation, 80m South of Orangedale Road to 50m North of Pomeroy Road, SLK 4.34 - 4.65	Asphalt overlay 20mm 5mm SMA	\$21,270	\$10,635	\$31,905
5	Abernethy Road, HW, Road Rehabilitation, 30m North of Lewis Rd to 40m South of Brinsmead Rd, SLK 6.30 - 6.54	Stabilise 275mm foamed bitumen & 40mm 14mm / 75 DG Asphalt	\$164,061	\$82,031	\$246,092
6	Welshpool Road East - Pavement Rehabilitation, Eastbound Lanes, 70m East of Roe Highway to 40m East of Crystal Brook Road, SLK 0.07 to 0.58	Lane 1 - Stabilise 300mm foamed bitumen & 40mm 14mm / 75 DG Asphalt Lane 2 - Mill and 40mm 14mm / 75 DG Asphalt	\$214,387	\$107,194	\$321,581
7	Welshpool Road East - Pavement Rehabilitation, Westbound Lanes, 70m East of Roe Highway to 40m East of Lewis Road, SLK 0.07 to 1.39	Part Lane 1 - Stabilise 300mm foamed bitumen & 40mm 14mm / 75 DG Asphalt Part Lane 1 and Lane 2 Mill and 40mm 14mm / 75 DG Asphalt	\$323,269	\$161,634	\$484,903
<b>Totals</b>			<b>\$1,451,702</b>	<b>\$725,851</b>	<b>\$2,177,553</b>